



स्थानिय सरकार
गुठिचौर गाउँपालिका
गाउँकार्यपालिकाको कार्यालय
धलमुडी, जुम्ला

कर्णाली प्रदेश

वडा कार्यालय भवन निर्माण सम्बन्धि सूचना


प्रथम पटक प्रकाशित मिति: २०८३।०३।०८



श्री निर्माण ब्यावसायीहरु सबै

प्रस्तुत विषयमा यस गुठीचौर गाउँपालिका जुम्लाको आर्थिक वर्ष २०८२।०८३ को स्वीकृत बजेट तथा क्रियाक्रम अनुसार वडा न ५ मा वडा कार्यालय भवन निर्माण गर्न विनियोजित भएको कन्टेन्जेन्सी बाहेक भ्याट सहित रु ९,४७,६३९।९० बजेटको सिमा भित्र रहेर काम गर्न इच्छुक यस गुठीचौर गाउँपालिकामा सुचिकृत भएका निर्माण व्यवसायीहरुले यो सूचना प्रकाशन भएको मितिले ७ दिन भित्र कार्यालय समयमा गुठीचौर गाउँपालिकाले तयार पारेको यसै साथ संलग्न BOQ को ढाचाँमा दररेट सहितको कोटेशन पेश गर्नु हुन सरोकारवालाहरुको जानकारीको लागि यो सूचना प्रकाशन गरिएको छ। काम गर्न इच्छुक निर्माण व्यवसायीहरुले माथी उल्लेखित समय भित्र गुठीचौर गाउँपालिकाको प्रशासन शाखामा खामबन्दि कोटेशन पेश गर्नुपर्ने छ। कोटेशन पेश गर्ने अन्तिम दिन बिदा परेमा त्यसको भोलिपल्ट कार्यालय समय भित्र पेश गर्नुपर्ने छ।

.....
टेक बहादुर बुढथापा
(प्रमुख प्रशासकीय अधिकृत)



गुठीचौर गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
धवलमडी जुम्ला
कर्णाली प्रदेश
कार्यालय कोड नं.



BILL OF QUANTITY

कार्यक्रम / आयोजनाको नाम: बडा कार्यालय भवन निर्माण
ठेगाना : गुठीचौर गाउँ पालिका बडा नं. ५ जुम्ला

FY=2082/083

Item NO.	Description of Works	Unit	Quantity	Rate NRS		Total Amount Nrs (₹.)	Remarks
				In Figures	In Words		
	1	2	3		4	5=3*4	6
1	Site Clearance After Complete the site	Sqm	90.00				
2	Stone soiling without sand	Cum	2.29				
3	Concreting of foundation, vert. faces,walls(cement conc.) incl. supply of materials & haulage distance upto 30m. P.C.C 1:2:4	Cum	1.49				
4	12.5mm thick cement sand plastering works.1:4 ratio	Sqm	301.90				
5	12.5mm thick cement sand plastering works. (On Ceiling) a) 1:3 ratio	Sqm	62.98				
6	Water proof cement paint application. (Snowceem)b. Two coat	Sqm	364.88				
7	Prepared enamel paint application. c. Second Coat	Sqm	26.16				
8	Construction of Gate using MS Angle frame of Different size with 14 to 18 gauge MS sheet, one coat primer and fitting complete	Kg	392.70				
9	Rubble masonry works included supply of hard stone blocks,preparing cement mortar & const.of wall upto 5m high.(Haulage upto 10m).1:4 cement sand mortar	Cum	6.89				
10	Concreting works of superstructures,deck slabs,beams including supply of materials & haulage dist. up to 30m.P.C.C 1:1.5:3	Cum	3.53				
11	In Column ,Erection, adjustment and nailing of forms for column incl. dismantle, removal and hauling up to 30m ,Local Wood (Sallo) Formwork	Sqm	40.32				
12	R.C.C Work-Cutting, bending, placing ,Cutting,bending, placing in position as shown in drawing & binding by G.I wire of reinforcement steel bars for RCC works included haulage distance of 30m. b) 10mm-20mm	Kg	566.16				
13	Miscellaneous works (Electrical works)	PS	1.00		Thirty Thousand only .	30,000.00	
14	Miscellaneous works (plumbing Toilet Pan , Works)	PS	1.00		Twentyfive Thousand only.	25,000.00	
				जम्मा लागत: (Total) A			
				VAT 13%			
				Grand Total			
In words:							

Firm Name :-
Address :-
Stamp :-
Contractor's Name :-
Sign :-
Date :-