



स्थानिय सरकार
गुठिचौर गाउँपालिका
गाउँकार्यपालिकाको कार्यालय
धलमुडी, जुम्ला

कर्णाली प्रदेश

वडा कार्यालय गेट निर्माण सम्बन्धि सूचना

प्रथम पटक प्रकाशित मिति: २०८३।०२।०६



श्री निर्माण ब्यावसायीहरु सबै

प्रस्तुत विषयमा यस गुठिचौर गाउँपालिका जुम्लाको आर्थिक वर्ष २०८२।०८३ को स्वीकृत बजेट तथा कार्यक्रम अनुसार वडा न १ को वडा कार्यालयको वडा कार्यालय गेट निर्माण गर्न बिनियोजित भएको कन्टेन्जेन्सी बाहेक भ्याट सहित रु ९१७२८८।२९ बजेटको सिमा भित्र रहेर काम गर्न इच्छुक यस गुठिचौर गाउँपालिकामा सुचिकृत भएका निर्माण व्यवसायीहरुले यो सूचना प्रकाशन भएको मितिले ७ दिन भित्र कार्यालय समयमा गुठिचौर गाउँपालिकाले तयार पारेको यसै साथ सँलग्न BOQ को ढाचाँमा दररेट सहितको कोटेशन पेश गर्नु हुन सरोकारवालाहरुको जानकारीको लागि यो सूचना प्रकाशन गरिएको छ। काम गर्न इच्छुक निर्माण व्यवसायीहरुले माथी उल्लेखित समय भित्र गुठिचौर गाउँपालिकाको प्रशासन शाखामा खामबन्दि कोटेशन पेश गर्नुपर्ने छ। कोटेशन पेश गर्ने अन्तिम दिन बिदा परेमा त्यसको भोलिपल्ट कार्यालय समय भित्र पेश गर्नुपर्ने छ।

[Handwritten signature]

२१६
टेक बहादुर बुढथापा
(प्रमुख प्रशासकीय अधिकृत)
प्रमुख प्रशासकीय अधिकृत



Guttichaur Rural Municipality
Office of Executive Municipality
Province Karnali
Dhawalnudi, Jumla.

BILL OF QUANTITY



संकेत नं./ अर्थवेतन नं.: नए. सं. संकेत नं. के बिना
संकेत नं.: १५५५/१

Item No.	Description of Works	Unit	Quantity	In Figures		Total Amount NRs.	Remarks
				In Figures	In Words		
1	Site Clearance	Sqm	21.00				
2	Excavation of soft clay & silty soils including disposal (Upto 10m lead & 1.5m lft.), (OS)	cum	29.63				
3	Stone soiling without sand	cum	8.55				
4	Stone masonry work including full compensation for all labour, materials and other incidentals required to complete the work as per the Specifications and drawings. (1:4 cis mortar)	cum	16.88				
5	Brick masonry works above Ground Floor alongwith supply of bricks making cement - sand mortar & const. of brick walls including Haulage up to 30m. -a) Machine Made Bricks 1:4 cement sand mortar	cum	0.19				
6	Cement Concrete Work, M 15 Grade (1:2:4 mix by volume)	cum	0.91				
7	PCC for Rec Work (1:1.5:3)	Cum	10.66				
8	12.5mm c.plaster - 1:4 for Wall	Sqm	37.09				
9	Construction of Gate using MS Angle Frame of Different size with 14 to 18 gauge MS sheet, one coat primer and fitting complete	kg	380.67				
10	Distemper paint works One coat.	sqm	20.05				
11	Water proof cement paint application. (Snowcem) Two coat	sqm	20.05				
12	RCC Reinforcement cutting, bending, placing, fixing in position	kg	271.79				
13	Erection, adjustment and nailing of forms for column Incl. dismantle, removal and hauling up to 30m. Local Wood (Sailo) Formwork	Sqm	9.80				
			Sub total				
			VAT (13% of Total)				
			GRAND TOTAL				

In words:

Firm Name :-

Address :-

Stamp :-

Sign :-

Date :-